OTC-09 | ENGINEERING & PROJECTS

Mechanical Commissioning & Start-Up Readiness

SUGGESTED DURATION: 3 DAYS | IN-COMPANY / LIVE ONLINE

Commissioning is an evidence-based transition from construction to operation. This course develops clear system boundaries, readiness checks and ownership of unresolved risks.

WHO SHOULD ATTEND

Project and construction engineers, commissioning teams, operations representatives and maintenance personnel accepting new equipment.

WHAT PARTICIPANTS WILL BE ABLE TO DO

- Distinguish mechanical completion, pre-commissioning, commissioning and performance testing.
- Identify preservation, cleanliness, alignment and protection-system readiness gaps.
- Prepare a documented handover and controlled start-up review.

SUGGESTED PROGRAMME OUTLINE

Day 1 | Plan the transition

Systemisation and battery limits; commissioning sequence and responsibilities; test packs, procedures and records; preservation and receipt inspection; mechanical completion and punch categorisation.

Day 2 | Pre-commissioning assurance

Flushing and cleanliness concepts; alignment and piping checks; lubrication and seal systems; instruments, trips and utilities; temporary items, reinstatement and permit/isolation interfaces.

Day 3 | Start-up and handover

Readiness review and operating procedures; initial monitoring and stop criteria; performance test basis; defect resolution; spares, drawings, manuals, training and final handover dossier.

OTC-09 | PRACTICAL APPLICATION & DELIVERY

Mechanical Commissioning & Start-Up Readiness

PRACTICAL WORKSHOPS

Ready to start?

Review an illustrative pump-package checklist and distinguish issues requiring closure from items eligible for authorised deferral.

Start-up abnormality

Investigate increasing bearing temperature after start-up and propose safe verification, escalation and handover records.

PARTICIPANT TOOLS AND TAKEAWAYS

Readiness checklist; system handover index; punch/action register; start-up monitoring sheet.

HOW LEARNING IS DELIVERED AND ASSESSED

Facilitated explanations, worked examples, case discussions and small-group exercises. A short baseline check establishes starting knowledge; a closing knowledge check and practical review assess learning. Assessment can be adapted for operators, technicians or experienced engineers.

CUSTOMISATION AND CLIENT INPUTS

Equipment P&IDs, vendor manuals and project completion workflow. Client procedures and authorised site personnel govern all field testing and start-up actions.

The agenda is indicative. Final content, duration, batch size, language and delivery arrangements are agreed after a training-needs discussion. Online delivery uses document reviews, calculations, role-play and case exercises; physical demonstrations require separate site arrangements.

FACILITATOR

Prem Prakash Mishra | Mechanical engineer, advisor and corporate trainer. Brings 39 years of career experience across Kuwait Oil Company, IPCL and NTPC, spanning projects, commissioning, maintenance, reliability, asset integrity and industrial audits. Specialist inputs, where needed, are agreed in the proposal.

COMPLETION AND FOLLOW-UP

An Omtech Corporation participation or completion certificate may be provided under the agreed assessment arrangements. This is company training, not an accredited professional qualification or a guarantee of certification. Post-training support is available with scope and duration agreed in the proposal.

REQUEST A CUSTOMISED TRAINING PROPOSAL

safehands@omtechcorporation.com

+91 9810772284 | +91 9987079111